

Braun's Painting, LLC

309 Kasson Road
Suite 1
Camillus, NY, 13031
United States

Tel 3157067828

Cell 315-706-7828

steve@braunspainting.com

braunspainting.com



PROPOSAL

Client	Steven Braun	Job#	1071
Address	309 Kasson Road Suite 1 Camillus, NY, 13031 US	Job	309 Kasson Road Suite 1 Camillus, NY, 13031 US
Tel	3157067828	Tel	3157067828
Email	steve@braunspainting.com	Email	steve@braunspainting.com
Submitted	1/4/2022 3:25 PM	Job Descr	Residential Interior
		Type	RESIDENTIAL INTERIOR

Foyer Entry & Stairway

We are NOT doing handrails or wall caps. We are painting the stringers, risers, and the window on the landing

We are painting the closet door, but not the entry door

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$300.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$278.07
Application of 1 coat of primer to all baseboard, casings, jambs, stair stringers			
Paint Trim		2	\$463.58
Materials: BM Regal Wall Paint: TBD			
Notes: Application of 2 coats of paint to baseboard, casing, jambs, and stair stringers.			
Materials			\$178.20
FOYER ENTRY & STAIRWAY SUBTOTAL			\$1,219.85

Living Room

Recaulk crown and paint lip only (wherever crown exists on first floor fill holes, caulk and finish coat on primed base.

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$240.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$238.35
Application of 1 coat of primer to all baseboard, casings, jambs, and fireplace mantle			
Paint Trim		2	\$397.36
Application of 2 coats of paint to baseboard, casing, jambs, and fireplace mantle			
Materials			\$0.00
LIVING ROOM SUBTOTAL			\$875.71

Dining Room

We are not painting the wainscot

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$90.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$79.45
Application of 1 coat of primer to all baseboard, casings, jambs			
Paint Trim		2	\$132.45
Application of 2 coats of paint to baseboard, casing, jambs			
Materials			\$0.00
DINING ROOM SUBTOTAL			\$301.90

Vestibule

Paint both sides of vestibule

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$180.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$99.31
Application of 1 coat of primer to all baseboard, casings, jambs			
Paint Trim		2	\$165.57
Application of 2 coats of paint to baseboard, casing, jambs			

Prime Doors	1	\$120.00
Materials:		
All-Prime Primer: white		
Notes:		
Application of 1 coat of primer to door(s)		
Paint Doors	2	\$180.00
Materials:		
BM Regal Wall Paint: TBD		
Notes:		
Applicatio of 2 coats of paint to door(s)		
Materials		\$23.27
VESTIBULE SUBTOTAL		\$768.15

Powder Room

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$120.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$59.59
Application of 1 coat of primer to all baseboard, casings, jambs			
Paint Trim		2	\$99.34
Application of 2 coats of paint to baseboard, casing, jambs			
Prime Doors		1	\$15.00
Materials:			
All-Prime Primer: white			
Notes:			
Application of 1 coat of primer to door(s)			
Paint Doors		2	\$30.00
Materials:			
BM Regal Wall Paint: TBD			
Notes:			
Applicatio of 2 coats of paint to door(s)			
Paint Walls		2	\$244.59
Materials:			
BM Regal Wall Paint:			
Notes:			
Application of 2 coats of paint to walls			
Materials			\$82.67
POWDER ROOM SUBTOTAL			\$651.19

Den

Don't forget pocket door

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$120.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$71.50
Application of 1 coat of primer to all baseboard, casings, jambs			
Paint Trim		2	\$119.21
Application of 2 coats of paint to baseboard, casing, jambs			
Prime Doors		1	\$15.00
Materials: All-Prime Primer: white			
Notes: Application of 1 coat of primer to door(s)			
Paint Doors		2	\$30.00
Materials: BM Regal Wall Paint: TBD			
Notes: Application of 2 coats of paint to door(s)			
Materials			\$23.27
DEN SUBTOTAL			\$378.98

Kitchen

Only stuff not painted already. Although do caulk cracked crown
Take note of breaking point going into family room, do NOT paint the window transition area in the middle. Block off with blue tape.

	NEW COLOR	#COATS	COST
Preparation & Cleanup		1	\$180.00
Includes cleaning, scuff sanding, and wipe down of trim prior to primer application. Also includes any necessary masking work and site protection. Also includes caulk work around baseboard and casing (as necessary)			
Prime Trim		1	\$103.28
Application of 1 coat of primer to all baseboard, casings, jambs			
Paint Trim		2	\$172.19
Application of 2 coats of paint to baseboard, casing, jambs			
Prime Doors		1	\$15.00
Materials: All-Prime Primer: white			
Notes: Application of 1 coat of primer to door(s)			

Paint Doors 2 \$30.00
Materials:
BM Regal Wall Paint: TBD
Notes:
Applicatio of 2 coats of paint to door(s)

Materials \$23.27

KITCHEN SUBTOTAL \$523.74

LABOR \$4,388.84

TAX \$351.11

LABOR SUBTOTAL \$4,739.95

MATERIALS \$330.68

TAX \$26.45

MATERIALS SUBTOTAL \$357.13

GRAND TOTAL \$5,097.08
