

Braun's Painting, LLC

309 Kasson Road
Suite 1
Camillus, NY, 13031
United States

Tel 3157067828
Cell 315-706-7828
steve@braunspainting.com
braunspainting.com



PROPOSAL

Client	Steven Braun	Job#	1078
Address	309 Kasson Road	Job	309 Kasson Road
	Suite 1	Address	Suite 1
	Camillus, NY, 13031		Camillus, NY, 13031
	US		US
Tel	3157067828	Tel	3157067828
Email	steve@braunspainting.com	Email	steve@braunspainting.com
Submitted	1/4/2022 5:11 PM	Job Descr	Residential Exterior
		Type	RESIDENTIAL EXTERIOR

Front of House



	NEW COLOR	#COATS	COST
Pressure Wash	NA	1	\$45.00
Pressure wash to remove dirt, mildew, insect webs, and any loose paint. Includes washing the gutters, aluminum fascia/soffit, and downspouts.			

Setup, Protection, & Cleanup	NA	1	\$180.00
<p>This includes jobsite protection of landscaping, concrete, windows, exterior equipment, etc. We will protect areas with drop clothes and plastic as needed, and any required shielding for spray work.</p> <p>This includes setup of ladders and equipment and project cleanup and debris removal.</p>			
Surface Preparation	NA	1	\$480.00
<p>Surface preparation includes application of caulk as needed around trim/windows, porch pillars, and all corner boards. Also includes any necessary scraping of areas with failing and flaking paint.</p> <p>This includes applying red-colored caulk to joint and seam cracks in the siding prior to paint application.</p> <p>Includes re-anchoring flower bed and putting house number back up with glue.</p>			
Paint Siding		1	\$625.82
<p>Materials:</p> <p>BM Regal Select Exterior Paint: TBD</p> <p>Notes:</p> <p>Application of 1 coat of Benjamin Moore Regal exterior paint to siding</p>			
Paint Trim		1	\$428.57
<p>Materials:</p> <p>BM Regal Select Exterior Paint: TBD</p> <p>Notes:</p> <p>Application of 1 coat of Benjamin Moore Regal exterior paint to all trim. This includes corner boards, porch trim and pillars, wood window casing.</p>			
Paint Door		2	\$105.00
<p>Materials:</p> <p>BM Regal Select Exterior Paint: TBD</p> <p>Notes:</p> <p>Application of 1 coat of paint to garage overhead door</p>			
Stain Foundation		1	\$120.00
<p>Materials:</p> <p>BM Arborcoat S/T Stain: TBD</p> <p>Notes:</p> <p>Application of 1 coat of concrete stain to foundation</p>			
Materials			\$356.10

FRONT OF HOUSE SUBTOTAL \$2,340.49

Left Side



	NEW COLOR	#COATS	COST
Pressure Wash	NA	1	\$31.50
Pressure wash to remove dirt, mildew, insect webs, and any loose paint. Includes washing the gutters, aluminum fascia/soffit, and downspouts.			
Setup, Protection, & Cleanup	NA	1	\$120.00
This includes jobsite protection of landscaping, concrete, windows, exterior equipment, etc. We will protect areas with drop clothes and plastic as needed, and any required shielding for spray work. This includes setup of ladders and equipment and project cleanup and debris removal.			
Surface Preparation	NA	1	\$300.00
Surface preparation includes application of caulk as needed around trim/windows, and all corner boards. Also includes any necessary scraping of areas with failing and flaking paint. This includes applying red-colored caulk to joint and seam cracks in the siding prior to paint application. Includes filling crack in foundation with masonry caulk.			
Paint Siding		1	\$430.25

Materials:

BM Regal Select Exterior Paint: TBD

Notes:

Application of 1 coat of Benjamin Moore Regal exterior paint to siding

Paint Trim	1	\$125.71
------------	---	----------

Materials:

BM Regal Select Exterior Paint: TBD

Notes:

Application of 1 coat of Benjamin Moore Regal exterior paint to all trim. This includes corner boards and door casing

Paint Door	2	\$45.00
------------	---	---------

Materials:

BM Regal Select Exterior Paint: TBD

Notes:

Application of 1 coat of paint to garage man door

Stain Foundation	1	\$75.00
------------------	---	---------

Materials:

BM Arborcoat S/T Stain: TBD

Notes:

Application of 1 coat of concrete stain to foundation

Materials		\$240.26
-----------	--	----------

LEFT SIDE SUBTOTAL		\$1,367.72
---------------------------	--	-------------------

Right Side



	NEW COLOR	#COATS	COST
Pressure Wash	NA	1	\$31.50

Pressure wash to remove dirt, mildew, insect webs, and any loose paint.
Includes washing the gutters, aluminum fascia/soffit, and downspouts.

Setup, Protection, & Cleanup	NA	1	\$60.00
<p>This includes jobsite protection of landscaping, concrete, windows, exterior equipment, etc. We will protect areas with drop clothes and plastic as needed, and any required shielding for spray work.</p> <p>This includes setup of ladders and equipment and project cleanup and debris removal.</p>			
Surface Preparation	NA	1	\$240.00
<p>Surface preparation includes application of caulk as needed around trim/windows, and all corner boards. Also includes any necessary scraping of areas with failing and flaking paint.</p> <p>This includes applying red-colored caulk to joint and seam cracks in the siding prior to paint application.</p> <p>Includes filling crack in foundation with masonry caulk.</p>			
Paint Siding		1	\$391.13
<p>Materials:</p> <p>BM Regal Select Exterior Paint: TBD</p> <p>Notes:</p> <p>Application of 1 coat of Benjamin Moore Regal exterior paint to siding</p>			
Paint Trim		1	\$108.57
<p>Materials:</p> <p>BM Regal Select Exterior Paint: TBD</p> <p>Notes:</p> <p>Application of 1 coat of Benjamin Moore Regal exterior paint to all trim. This includes corner boards</p>			
Stain Foundation		1	\$75.00
<p>Materials:</p> <p>BM Arborcoat S/T Stain: TBD</p> <p>Notes:</p> <p>Application of 1 coat of concrete stain to foundation</p>			
Materials			\$191.89
RIGHT SIDE SUBTOTAL			\$1,098.09

Back of House



	NEW COLOR	#COATS	COST
Pressure Wash	NA	1	\$90.00
Pressure wash to remove dirt, mildew, insect webs, and any loose paint. Includes washing the gutters, aluminum fascia/soffit, and downspouts. Includes washing the deck and railing.			
Setup, Protection, & Cleanup	NA	1	\$480.00
This includes jobsite protection of landscaping, concrete, windows, exterior equipment, etc. We will protect areas with drop clothes and plastic as needed, and any required shielding for spray work. This includes setup of ladders and equipment and project cleanup and debris removal.			
Surface Preparation	NA	1	\$360.00
Surface preparation includes application of caulk as needed around trim/windows, porch pillars, and all corner boards. Also includes any necessary scraping of areas with failing and flaking paint. This includes applying red-colored caulk to joint and seam cracks in the siding prior to paint application. Includes cutting out the rotted section of vertical board on the screen porch, and replacing that with a composite material to avoid rotting from water absorption from the deck.			
Carpentry Repairs	NA	1	\$360.00

This includes removal of rotted trim (window sills or casings as applicable), and installation of new PVC trim of matching profile.



Paint Siding	1	\$625.82
Materials:		
BM Regal Select Exterior Paint: TBD		
Notes:		
Application of 1 coat of Benjamin Moore Regal exterior paint to siding		
Paint Trim	1	\$457.14
Materials:		
BM Regal Select Exterior Paint: TBD		
Notes:		
Application of 1 coat of Benjamin Moore Regal exterior paint to all trim. This includes corner boards, screened porch, wood window casing.		
Stain Foundation	1	\$120.00
Materials:		
BM Arborcoat S/T Stain: TBD		
Notes:		
Application of 1 coat of concrete stain to foundation		
Materials		\$327.98
BACK OF HOUSE SUBTOTAL		\$2,820.94

	LABOR	\$6,511.01
	TAX	\$520.88
	<hr/>	
	LABOR SUBTOTAL	\$7,031.89
	MATERIALS	\$1,116.23
	TAX	\$89.30
	<hr/>	
	MATERIALS SUBTOTAL	\$1,205.53
	GRAND TOTAL	\$8,237.42
